Emergency Detour Route Repair Areas

Road	Repair Location	Estimated Repair Quantity (Removal of Asphalt Pavement Partial Depth, 50mm; Pave SP12.5FC2, 50mm)
Stevensville Road (116)	From the north edge of Foster Street to 50m north of Foster Street, southbound lane only.	50 m long x 4 m wide = 200 m^2
	From the north edge of Foster Street to 20m south of Foster Street, northbound lane only.	20 m long x 4 m wide = 80 m^2
Garrison Road (3)	Strip mill (1 m wide) from 5 m west of the west curb line of Buffalo Road to 55 m west of the west curb line of Buffalo Road, eastbound lane 1, right wheel path.	50 m long x 1 m wide = 50 m^2
	Strip mill (1 m wide) from the east edge of Municipal Drive to 140 m west of the east edge of Municipal Drive, starting between eastbound lane 1 and eastbound lane 2, moving into eastbound lane 2 westerly.	140 m long x 1 m wide = 140 m^2
	Strip mill (1 m wide) from Rose Hill Road easterly for 380 m in eastbound lane 1, right wheel path.	380 m long x 1 m wide = 380 m^2
	Total Quantity	850 m^2