SOIL-MAT ENGINEERS & CONSULTANTS LTD.

www.soilmat.ca info@soilmat.ca TF: 800.243.1922

Hamilton: 130 Lancing Drive L8W 3A1 T: 905.318.7440 F: 905.318.7455
Milton: PO Box 40012 Derry Heights PO L9T 7W4 T: 905.875.3228

PROJECT NO.: SM 188418-E

June 12, 2018

Facilities Management Services
Niagara College
100 Niagara College Boulevard
Welland, Ontario
L3C 7L3

Attention: Bartholomew Lanni

ENVIRONMENTAL SOIL TESTING
EAST PARKING LOT – NIAGARA COLLEGE NOTL CAMPUS
NIAGARA-ON-THE-LAKE, ONTARIO

Dear Mr. Lanni,

As per your request, a representative of SOIL-MAT ENGINEERS & CONSULTANTS LTD. visited the above noted site on June 5, 2018. The purpose of our site visit was to secure representative soil samples for submission for analytical testing and to provide interpretation of these test results with respect to the off-site disposal of the subject material. It is understood that as part of the proposed parking lot reconstruction there will be some volume of subgrade soils which will be removed, and require off-site disposal.

A representative of SOIL-MAT ENGINEERS secured five [5] representative samples of the subsurface soil material from the site. The samples were recovered via machine augered test holes, advanced by Niagara College staff, and a hand augered test hole from a depth of approximately 0.9 metres below ground surface at the locations requested by the client as illustrated in the attached Drawing No. 1, Sample Location Plan. The sampled material was noted to consist of brown silty clay with trace sand and gravel. No evidence of potential petroleum hydrocarbon impact, i.e. odour, staining, etc., was noted at the time of sampling. The soil samples were submitted to AGAT Laboratories [AGAT], [an accredited Canadian Environmental Laboratory] for a standard panel of metals and inorganics.

The laboratory test results received in our Office were compared with the applicable standard from the Soil, Ground Water and Sediment Standards for Use Under Part XV.1 of the *Environmental Protection Act*, as follows:

- **ONTARIO REGULATION 1 53/04 – TABLE 1**: Full Depth Background Site Condition Standards Residential/Parkland/Institutional and Industrial/Commercial/Community land use.
- **ONTARIO REGULATION 153/04 – TABLE 2**: Full Depth Generic Site Condition Standards Residential/Parkland/Institutional and Industrial/Commercial/Community land use in a potable groundwater condition.
- **ONTARIO REGULATION 153/04 – TABLE 3**: Full Depth Generic Site Condition /Standards Residential/Parkland/Institutional and Industrial/Commercial/Community land use in a non-potable groundwater condition.

The results of this laboratory testing are presented in the attached AGAT Certificate of Analysis [AGAT Work Order Number-18H346837].

Based on SOIL-MAT'S field observations and the analytical test results from AGAT, SOIL-MAT offers the following comments:

1. The sampled material was found to be within the Table 1 [ALL] Standards for the tested parameters with the exception of Electric Conductivity [EC] and Sodium Absorption Ratio [SAR] in samples 'S2' and 'S4'.
2. The sampled material was found to be within the Table 2 and 3 [RPI] Standards for the tested parameters with the exception of EC and SAR in samples 'S2' and 'S4'.
3. The sampled material was found to be within the Table 2 and 3 [ICC] Standards for the tested parameters with the exception of EC and SAR in samples 'S2' and 'S4'.
4. It is noted that elevated EC and SAR is typically associated with the effects of the application of de-icing salt on parking areas and roadways. These are essentially aesthetic parameters that are non-hazardous to human or animal health, rather they tend to render the soil environment less supportive of plant growth and more corrosive the buried pipe.
5. The soil samples secured for analytical testing are believed to be representative of the soil conditions at the sample locations only. If any significant changes are noted, i.e., odours, staining etc., SOIL-MAT ENGINEERS & CONSULTANTS LTD. should be contacted to reassess the environmental characteristics of the soil.

Given the above test results the following disposal options are applicable under Regulation 153/04 [amended by Regulation 511/09 effective July 1, 2011].

- As the tested material has been shown to exceed the Table 1 Standards for the parameters tested, surplus material may not be accepted at an off-site property subject to a Record of Site Condition or MOE Certificate of Authorisation.

- As the tested material has been shown to exceed the Table 2 and 3 [RPI] Standards for the parameters tested, strictly speaking surplus material may not be accepted at an off-site RPI property in a potable or non-potable groundwater condition
    - However, the tested material only has elevated levels for EC and SAR, which as noted above are essentially aesthetic parameters that do not pose a risk to human health. As such the subject material may be reasonably accepted at an off-site Table 2 or 3 [RPI] property under the MOEs 'beneficial use' concept, subject to approval of the receiving property owner. Such reuse would require clear identification of the end use of the material and may require further evaluation of the proposed receiving site.
- As the tested material has been shown to exceed the Table 2 and 3 [ICC] Standards for the parameters tested, strictly speaking surplus material may not be accepted at an off-site ICC property in a potable or non-potable groundwater condition.
    - However, the tested material only has elevated levels for EC and SAR, which as noted above are essentially aesthetic parameters that do not pose a risk to human health. As such the subject material may be reasonably accepted at an off-site Table 2 or 3 [ICC] property under the MOEs 'beneficial use' concept, subject to approval of the receiving property owner. Such reuse would require clear identification of the end use of the material and may require further evaluation of the proposed receiving site.
- As the tested material has been shown to exceed Excavated soil may be reused on site.

We trust this is satisfactory for your purposes. Please feel free to contact our Office if you have any questions, or we may be of further service to you.

Yours very truly,
SOIL-MAT ENGINEERS & CONSULTANTS LTD.


Ross Keiller
Environmental Technician

Ian Shaw, P.Eng., QP_{ESA}
Senior Engineer

LICENSED PROFESSIONAL ENGINEER
JUNE 12/18
L. D. SHAW
100042315
PROVINCE OF ONTARIO

Enclosures: Drawing No. 1, Sample Location Plan [1 Page]
AGAT Certificate of Analysis 18H346837 [6 Pages]

Distribution: Niagara College [1, plus pdf]



LEGEND

S# = Sample Location

NOTES:

1. This map should be read in conjunction with Soil-Mat Engineers and Consultants Ltd. Report No.: SM 188418-E

2. Sample locations are approximate.

3. Drawing not to scale.

Soil-Mat
Engineers & Consultants Ltd.

CLIENT
NIAGARA COLLEGE

PROJECT TITLE
Environmental Soil Testing
East Parking Lot
Niagara College - NOTL Campus
Niagara-on-the -Lake, Ontario

DRAWING TITLE
Sample Location Plan

PROJECT No.	SM 188418-E
DATE	June 2018
CHECKED	IS
DRAWN	RK
FILE NAME	188418 Sample location plan .vsdx

DRAWING No. 1

AGAT Laboratories

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
http://www.agatlabs.com

CLIENT NAME: SOIL MAT ENGINEERS & CONSULTANTS LT
130 LANCING DRIVE
HAMILTON, ON L8W3A1
(905) 318-7440

ATTENTION TO: Ian Shaw

PROJECT: NC NOTL

AGAT WORK ORDER: 18H346837

SOIL ANALYSIS REVIEWED BY: Amanjot Bhela, Inorganic Coordinator

DATE REPORTED: Jun 11, 2018

PAGES (INCLUDING COVER): 6

VERSION*: 1

Should you require any information regarding this analysis please contact your client services representative at (905) 712-5100

*NOTES

All samples will be disposed of within 30 days following analysis. Please contact the lab if you require additional sample storage time.

Member of: Association of Professional Engineers and Geoscientists of Alberta (APEGA)
Western Enviro-Agricultural Laboratory Association (WEALA)
Environmental Services Association of Alberta (ESAA)

AGAT Laboratories is accredited to ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA) and/or Standards Council of Canada (SCC) for specific tests listed on the scope of accreditation. AGAT Laboratories (Mississauga) is also accredited by the Canadian Association for Laboratory Accreditation Inc. (CALA) for specific drinking water tests. Accreditations are location and parameter specific. A complete listing of parameters for each location is available from www.cala.ca and/or www.scc.ca. The tests in this report may not necessarily be included in the scope of accreditation.

Results relate only to the items tested and to all the items tested
All reportable information as specified by ISO 17025:2005 is available from AGAT Laboratories upon request

AGAT Laboratories

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
http://www.agatlabs.com

Certificate of Analysis

AGAT WORK ORDER: 18H346837

PROJECT: NC NOTL

CLIENT NAME: SOIL MAT ENGINEERS & CONSULTANTS LT

ATTENTION TO: Ian Shaw

SAMPLING SITE:

SAMPLED BY:

O. Reg. 153(511) - Metals & Inorganics (Soil)

DATE RECEIVED: 2018-06-05

DATE REPORTED: 2018-06-11

		SAMPLE DESCRIPTION:		S1	S2	S3	S4	S5
		SAMPLE TYPE:		Soil	Soil	Soil	Soil	Soil
		DATE SAMPLED:		2018-06-05	2018-06-05	2018-06-05	2018-06-05	2018-06-05
Parameter	Unit	G / S	RDL	9299549	9299555	9299557	9299558	9299563
Antimony	µg/g	1.3	0.8	<0.8	<0.8	<0.8	<0.8	<0.8
Arsenic	µg/g	18	1	5	5	6	6	7
Barium	µg/g	220	2	137	169	156	146	86
Beryllium	µg/g	2.5	0.5	0.6	0.7	0.7	0.7	<0.5
Boron	µg/g	36	5	8	9	9	<5	<5
Boron (Hot Water Soluble)	µg/g	NA	0.10	0.11	0.16	0.33	0.22	0.41
Cadmium	µg/g	1.2	0.5	<0.5	<0.5	<0.5	0.7	0.6
Chromium	µg/g	70	2	28	32	31	36	23
Cobalt	µg/g	21	0.5	13.2	16.1	15.1	14.1	8.3
Copper	µg/g	92	1	25	27	26	27	24
Lead	µg/g	120	1	11	12	11	21	40
Molybdenum	µg/g	2	0.5	<0.5	<0.5	<0.5	0.7	0.8
Nickel	µg/g	82	1	28	33	32	28	19
Selenium	µg/g	1.5	0.4	<0.4	<0.4	<0.4	0.5	0.5
Silver	µg/g	0.5	0.2	<0.2	<0.2	<0.2	0.2	0.2
Thallium	µg/g	1	0.4	<0.4	<0.4	<0.4	<0.4	<0.4
Uranium	µg/g	2.5	0.5	0.6	0.7	0.8	0.7	0.6
Vanadium	µg/g	86	1	37	43	41	41	29
Zinc	µg/g	290	5	64	71	70	92	85
Chromium VI	µg/g	0.66	0.2	<0.2	<0.2	<0.2	<0.2	<0.2
Cyanide	µg/g	0.051	0.040	<0.040	<0.040	<0.040	<0.040	<0.040
Mercury	µg/g	0.27	0.10	<0.10	<0.10	<0.10	<0.10	<0.10
Electrical Conductivity	mS/cm	0.57	0.005	0.309	**4.15**	0.429	**1.18**	0.324
Sodium Adsorption Ratio	NA	2.4	NA	0.440	**23.7**	0.727	**7.03**	0.593
pH, 2:1 CaCl2 Extraction	pH Units		NA	7.91	7.96	7.90	7.65	7.66

Comments: RDL - Reported Detection Limit; G / S - Guideline / Standard: Refers to Table 1: Full Depth Background Site Condition Standards - Soil - Residential/Parkland/Institutional/Industrial/Commercial/Community Property Use
Guideline values are for general reference only. The guidelines provided may or may not be relevant for the intended use. Refer directly to the applicable standard for regulatory interpretation.

9299549-9299563 EC & SAR were determined on the DI water extract obtained from the 2:1 leaching procedure (2 parts DI water:1 part soil). pH was determined on the 0.01M CaCl2 extract prepared at 2:1 ratio.

Certified By: Amanjot Bhela

Results relate only to the items tested and to all the items tested

AGAT Laboratories

Guideline Violation

AGAT WORK ORDER: 18H346837

PROJECT: NC NOTL

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
http://www.agatlabs.com

CLIENT NAME: SOIL MAT ENGINEERS & CONSULTANTS LT

ATTENTION TO: Ian Shaw

SAMPLEID	SAMPLE TITLE	GUIDELINE	ANALYSIS PACKAGE	PARAMETER	UNIT	GUIDEVALUE	RESULT
9299555	S2	ON T1 S RPI/ICC	O. Reg. 153(511) - Metals & Inorganics (Soil)	Electrical Conductivity	mS/cm	0.57	4.15
9299555	S2	ON T1 S RPI/ICC	O. Reg. 153(511) - Metals & Inorganics (Soil)	Sodium Adsorption Ratio	NA	2.4	23.7
9299558	S4	ON T1 S RPI/ICC	O. Reg. 153(511) - Metals & Inorganics (Soil)	Electrical Conductivity	mS/cm	0.57	1.18
9299558	S4	ON T1 S RPI/ICC	O. Reg. 153(511) - Metals & Inorganics (Soil)	Sodium Adsorption Ratio	NA	2.4	7.03

Results relate only to the items tested and to all the items tested

AGAT Laboratories
5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
http://www.agatlabs.com

Quality Assurance

CLIENT NAME: SOIL MAT ENGINEERS & CONSULTANTS LT

AGAT WORK ORDER: 18H346837

PROJECT: NC NOTL

ATTENTION TO: Ian Shaw

SAMPLING SITE:

SAMPLED BY:

Soil Analysis

RPT Date:			DUPLICATE				REFERENCE MATERIAL			METHOD BLANK SPIKE			MATRIX SPIKE		
PARAMETER	Batch	Sample Id	Dup #1	Dup #2	RPD	Method Blank	Measured Value	Acceptable Limits		Recovery	Acceptable Limits		Recovery	Acceptable Limits	
								Lower	Upper		Lower	Upper		Lower	Upper
O. Reg. 153(511) - Metals & Inorganics (Soil)															
Antimony	9299549	9299549	<0.8	<0.8	NA	< 0.8	100%	70%	130%	88%	80%	120%	85%	70%	130%
Arsenic	9299549	9299549	5	5	0.0%	< 1	106%	70%	130%	97%	80%	120%	97%	70%	130%
Barium	9299549	9299549	137	145	5.7%	< 2	108%	70%	130%	95%	80%	120%	94%	70%	130%
Beryllium	9299549	9299549	0.6	0.6	NA	< 0.5	78%	70%	130%	103%	80%	120%	75%	70%	130%
Boron	9299549	9299549	8	8	NA	< 5	86%	70%	130%	101%	80%	120%	92%	70%	130%
Boron (Hot Water Soluble)	9299549	9299549	0.11	0.13	NA	< 0.10	90%	60%	140%	93%	70%	130%	94%	60%	140%
Cadmium	9299549	9299549	<0.5	<0.5	NA	< 0.5	97%	70%	130%	100%	80%	120%	93%	70%	130%
Chromium	9299549	9299549	28	29	3.5%	< 2	89%	70%	130%	99%	80%	120%	95%	70%	130%
Cobalt	9299549	9299549	13.2	14.2	7.3%	< 0.5	98%	70%	130%	95%	80%	120%	92%	70%	130%
Copper	9299549	9299549	25	27	7.7%	< 1	93%	70%	130%	103%	80%	120%	108%	70%	130%
Lead	9299549	9299549	11	12	8.7%	< 1	107%	70%	130%	100%	80%	120%	109%	70%	130%
Molybdenum	9299549	9299549	<0.5	<0.5	NA	< 0.5	97%	70%	130%	105%	80%	120%	99%	70%	130%
Nickel	9299549	9299549	28	30	6.9%	< 1	95%	70%	130%	94%	80%	120%	73%	70%	130%
Selenium	9299549	9299549	<0.4	<0.4	NA	< 0.4	105%	70%	130%	96%	80%	120%	95%	70%	130%
Silver	9299549	9299549	<0.2	<0.2	NA	< 0.2	98%	70%	130%	97%	80%	120%	87%	70%	130%
Thallium	9299549	9299549	<0.4	<0.4	NA	< 0.4	99%	70%	130%	94%	80%	120%	89%	70%	130%
Uranium	9299549	9299549	0.6	0.6	NA	< 0.5	103%	70%	130%	96%	80%	120%	94%	70%	130%
Vanadium	9299549	9299549	37	39	5.3%	< 1	93%	70%	130%	96%	80%	120%	97%	70%	130%
Zinc	9299549	9299549	64	68	6.1%	< 5	100%	70%	130%	104%	80%	120%	90%	70%	130%
Chromium VI	9311007		<0.2	<0.2	NA	< 0.2	70%	70%	130%	104%	80%	120%	109%	70%	130%
Cyanide	9300427		<0.040	<0.040	NA	< 0.040	99%	70%	130%	101%	80%	120%	103%	70%	130%
Mercury	9299549	9299549	<0.10	<0.10	NA	< 0.10	103%	70%	130%	92%	80%	120%	94%	70%	130%
Electrical Conductivity	9299549	9299549	0.309	0.302	2.3%	< 0.005	95%	90%	110%	NA			NA		
Sodium Adsorption Ratio	9299549	9299549	0.440	0.453	2.9%	NA	NA			NA			NA		
pH, 2:1 CaCl2 Extraction	9309967		7.56	7.57	0.1%	NA	100%	80%	120%	NA			NA		

Comments: NA signifies Not Applicable.
Duplicate Qualifier: As the measured result approaches the RL, the uncertainty associated with the value increases dramatically, thus duplicate acceptance limits apply only where the average of the two duplicates is greater than five times the RL.

Certified By: Amanjot Bhela

AGAT Laboratories is accredited to ISO/IEC 17025 by the Canadian Association for Laboratory Accreditation Inc. (CALA) and/or Standards Council of Canada (SCC) for specific tests listed on the scope of accreditation. AGAT Laboratories (Mississauga) is also accredited by the Canadian Association for Laboratory Accreditation Inc. (CALA) for specific drinking water tests. Accreditations are location and parameter specific. A complete listing of parameters for each location is available from www.cala.ca and/or www.scc.ca. The tests in this report may not necessarily be included in the scope of accreditation.

Results relate only to the items tested and to all the items tested

AGAT Laboratories

5835 COOPERS AVENUE
MISSISSAUGA, ONTARIO
CANADA L4Z 1Y2
TEL (905)712-5100
FAX (905)712-5122
http://www.agatlabs.com

Method Summary

CLIENT NAME: SOIL MAT ENGINEERS & CONSULTANTS LT

AGAT WORK ORDER: 18H346837

PROJECT: NC NOTL

ATTENTION TO: Ian Shaw

SAMPLING SITE:

SAMPLED BY:

PARAMETER	AGAT S.O.P	LITERATURE REFERENCE	ANALYTICAL TECHNIQUE
Soil Analysis			
Antimony	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Arsenic	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Barium	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Beryllium	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Boron	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Boron (Hot Water Soluble)	MET-93-6104	EPA SW 846 6010C; MSA, Part 3, Ch.21	ICP/OES
Cadmium	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Chromium	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Cobalt	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Copper	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Lead	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Molybdenum	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Nickel	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Selenium	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Silver	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Thallium	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Uranium	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Vanadium	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Zinc	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Chromium VI	INOR-93-6029	SM 3500 B; MSA Part 3, Ch. 25	SPECTROPHOTOMETER
Cyanide	INOR-93-6052	MOE CN-3015 & E 3009 A;SM 4500 CN	TECHNICON AUTO ANALYZER
Mercury	MET-93-6103	EPA SW-846 3050B & 6020A	ICP-MS
Electrical Conductivity	INOR-93-6036	McKeague 4.12, SM 2510 B	EC METER
Sodium Adsorption Ratio	INOR-93-6007	McKeague 4.12 & 3.26 & EPA SW-846 6010C	ICP/OES
pH, 2:1 CaCl2 Extraction	INOR-93-6031	MSA part 3 & SM 4500-H+ B	PH METER

Results relate only to the items tested and to all the items tested

AGAT Laboratories

5835 Coopers Avenue
Mississauga, Ontario L4Z 1Y2
Ph: 905.712.5100 Fax: 905.712.5122
webearth.agatlabs.com

Chain of Custody Record

If this is a Drinking Water sample, please use Drinking Water Chain of Custody Form (potable water consumed by humans)

Laboratory Use Only

Work Order #: 18H346537

Cooler Quantity: 1 BAG

Arrival Temperatures: 19.7 | 19.6 | 19.4

Custody Seal Intact: ☐ Yes ☐ No ☐ N/A

Notes: ON ICE

Report Information:

Company: Soilmat

Contact:

Address: 130 Lancing Dr Hamilton

Phone: Fax:

Reports to be sent to:

1. Email: Ross Keil

2. Email: Ian Shaw

Regulatory Requirements: ☐ No Regulatory Requirement

(Please check all applicable boxes)

☒ Regulation 153/04 — Table 1 (Indicate One) ☐ Ind/Com ☐ Res/Park ☐ Agriculture

Soil Texture (Check One) ☐ Coarse ☐ Fine

☐ Sewer Use ☐ Sanitary ☐ Storm

Region ____ (Indicate One) ☐ MISA

☐ Regulation 558 ☐ CCME ☐ Prov. Water Quality Objectives (PWQO) ☐ Other ____ (Indicate One)

Is this submission for a **Record of Site Condition?** ☐ Yes ☐ No

Report Guideline on *Certificate of Analysis* ☐ Yes ☐ No

Turnaround Time (TAT) Required:

Regular TAT ☐ 5 to 7 Business Days

Rush TAT (Rush Surcharges Apply)

☐ 3 Business Days ☐ 2 Business Days ☐ Next Business Day

OR Date Required (Rush Surcharges May Apply): 5 day

Please provide prior notification for rush TAT

**TAT is exclusive of weekends and statutory holidays*

For 'Same Day' analysis, please contact your AGAT CPM

Project Information:

Project: NC NOTL

Site Location: Niagara College NOTL Rue

Sampled By:

AGAT Quote #: PO:

Please note: If quotation number is not provided, client will be billed full price for analysis.

Invoice Information:

Bill To Same: Yes ☐ No ☐

Company:

Contact:

Address:

Email:

Sample Matrix Legend

B	Biota
GW	Ground Water
O	Oil
P	Paint
S	Soil
SD	Sediment
SW	Surface Water

Sample Identification	Date Sampled	Time Sampled	# of Containers	Sample Matrix	Comments/ Special Instructions	Field Filtered - Metals, Hg, CrVI (Y/N)	O. Reg 153: Metals and Inorganics (☐ All Metals ☐ 153 Metals (excl. Hydrides) ☐ Hydride Metals ☐ 153 Metals (Incl. Hydrides))	ORPs: ☐ B-HWS ☐ Cl⁻ ☐ CN⁻ ☐ Cr^{6+} ☐ EC ☐ FOC ☐ Hg ☐ pH ☐ SAR	Full Metals Scan	Regulation/Custom Metals	Nutrients: ☐ TP ☐ NH_3 ☐ TKN ☐ NO_3 ☐ NO_2 ☐ NO_3+NO_2	Volatiles: ☐ VOC ☐ BTEX ☐ THM	PHCs F1 - F4	ABNs	PAHs	PCBs: ☐ Total ☐ Aroclors	Organochlorine Pesticides	TCLP: ☐ M&I ☐ VOCs ☐ ABNs ☐ B(a)P ☐ PCBs	Sewer Use
S1	Jun 5/18	Am	1	S			X												
S2	↓	↓	1	↓			X												
S3			1				X												
S4			1				X												
S5			1				X												

Samples Relinquished By (Print Name and Sign):	Date	Time	Samples Received By (Print Name and Sign):	Date	Time
Ross Keil	Jun 5/18	2:45	Daniella Jaic	June 5/18	2:45pm

Page 1 of 1

N°: T 071075